

BRUHAT BENGALURU MAHANAGARA PALIKE

Construction of CC roads and other works at Shettyhalli colony balance roads in ward No.12, Shettyhalli Sub-division.

Ward No 12 - Shettyhalli.

SL. No. 04, G O No. 86 (Package No - DHZ 01)

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
1	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 &M-20. MORTH Specification No. 202 (PW,P& IWTD SR 2018-19, Pg No 139 Item No.18.20)										
	Dismantling of drain Slabs										
	Main road	0.00	200.00	Cum	1	200.00	0.90		180.00		
	1st cross road	0.00	85.00	Cum	2	85.00	0.90		153.00		
	2nd cross road	0.00	130.00	Cum	2	130.00	0.90		234.00		
	3rd cross road	0.00	110.00	Cum	2	110.00	0.90		198.00		
	5th cross road	0.00	30.00	Cum	1	30.00	0.90		27.00		
	6th cross road	0.00	50.00	Cum	1	50.00	0.90		45.00		
									837.00		
	Cosidering 30% for Dismalting								251.10	413.40	1,03,804.74
2	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH I Chapter 3(PW,P& IWTD SR 2018-19, Pg No 143 Item No. 19.1)										
	Desilting of Drain										
	Main road RHS	0.00	200.00	Cum	1	200.00	0.80	0.50	80.00		
	1st cross road	0.00	85.00	Cum	2	85.00	0.80	0.50	68.00		
	2nd cross road	0.00	130.00	Cum	2	130.00	0.80	0.50	104.00		
	3rd cross road	0.00	110.00	Cum	2	110.00	0.80	0.50	88.00		
	5th cross road	0.00	30.00	Cum	1	30.00	0.80	0.50	12.00		
	6th cross road	0.00	50.00	Cum	1	50.00	0.80	0.50	20.00		
	Earthwork for Kerb										
	Main road	0.00	200.00	Cum	1	200.00	0.20	0.10	4.00		
	1st cross road	0.00	85.00	Cum	2	85.00	0.20	0.10	3.40		
	2nd cross road	0.00	130.00	Cum	2	130.00	0.20	0.10	5.20		
	3rd cross road	0.00	110.00	Cum	2	110.00	0.20	0.10	4.40		
	5th cross road	0.00	30.00	Cum	1	30.00	0.20	0.10	0.60		
	6th cross road	0.00	50.00	Cum	1	50.00	0.20	0.10	1.00		
	RWH @ every 100m interval			Cum	15	0.31		1.80	8.42		
	Abbigere colony										
	Desilting of Drain										
	1st A cross road	0.00	28.50	Cum	2	28.50	0.80	0.30	13.68		
	3rd A cross road	0.00	40.00	Cum	2	40.00	0.80	0.30	19.20		
	4th A cross road	0.00	31.00	Cum	2	31.00	0.80	0.30	14.88		
	6th cross road (RHS)	0.00	59.00	Cum	2	59.00	0.80	0.30	28.32		
	Earthwork for Kerb										
	1st A cross road	0.00	28.50	Cum	2	28.50	0.20	0.10	1.14		
	3rd A cross road	0.00	40.00	Cum	2	40.00	0.20	0.10	1.60		
	4th A cross road	0.00	31.00	Cum	2	31.00	0.20	0.10	1.24		
	6th cross road (RHS)	0.00	59.00	Cum	2	59.00	0.20	0.10	2.36		
									481.44	137.80	66,342.11

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
3	KSRB 4-1.7: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (PW,P& IWTDR SR 2018-19 P-13, I-4.7)										
	M10 Concrete - PCC For Kerb										
	Main road	0.00	200.00	Cum	1	200.00	0.20	0.10	4.00		
	1st cross road	0.00	85.00	Cum	2	85.00	0.20	0.10	3.40		
	2nd cross road	0.00	130.00	Cum	2	130.00	0.20	0.10	5.20		
	3rd cross road	0.00	110.00	Cum	2	110.00	0.20	0.10	4.40		
	5th cross road	0.00	30.00	Cum	1	30.00	0.20	0.10	0.60		
	6th cross road	0.00	50.00	Cum	1	50.00	0.20	0.10	1.00		
	Abbigere colony										
	M10 Concrete - PCC For Kerb										
	1st A cross road	0.00	28.50	Cum	2	28.50	0.20	0.10	1.14		
	3rd A cross road	0.00	40.00	Cum	2	40.00	0.20	0.10	1.60		
	4th A cross road	0.00	31.00	Cum	2	31.00	0.20	0.10	1.24		
	6th cross road (RHS)	0.00	59.00	Cum	2	59.00	0.20	0.10	2.36		
									24.94	5714.97	1,42,531.27
4	Removing and resetting of footpath slab (PW,P & IWTDR SR 2018-19, Item No.37.56, Page No.270)										
	For Drain Cover Slabs										
	Main road	0.00	200.00	Sqm	1	200.00	0.90		180.00		
	1st cross road	0.00	85.00	Sqm	2	85.00	0.90		153.00		
	2nd cross road	0.00	130.00	Sqm	2	130.00	0.90		234.00		
	3rd cross road	0.00	110.00	Sqm	2	110.00	0.90		198.00		
	5th cross road	0.00	30.00	Sqm	1	30.00	0.90		27.00		
	6th cross road	0.00	50.00	Sqm	1	50.00	0.90		45.00		
	Total								837.00		
	CONSIDERING 70% FOR REMOVING AND RESETTNG								585.90		
	Abbigere colony										
	1st A cross road	0.00	28.50	Sqm	2	28.50	0.90		51.30		
	3rd A cross road	0.00	40.00	Sqm	2	40.00	0.90		72.00		
	4th A cross road	0.00	31.00	Sqm	2	31.00	0.90		55.80		
	6th cross road (RHS)	0.00	59.00	Sqm	2	59.00	0.90		106.20		
	Total								871.20	208.82	1,81,923.98
5	KSRB 15.2.2 : Providing ruled pointing 20 mm deep to stone slab pavements with cement mortar 1:3, 20mm deep, after raking joints nicely lining, including cost of materials, labour, curing complete as per specifications. (PW,P& IWTDR SR 2018-19 P-115, I-15.8)										
	Pointing for resetting slabs										
	Main road	0.00	200.00	Sqm	1	200.00	0.90		180.00		
	1st cross road	0.00	85.00	Sqm	2	85.00	0.90		153.00		
	2nd cross road	0.00	130.00	Sqm	2	130.00	0.90		234.00		
	3rd cross road	0.00	110.00	Sqm	2	110.00	0.90		198.00		
	5th cross road	0.00	30.00	Sqm	1	30.00	0.90		27.00		
	6th cross road	0.00	50.00	Sqm	1	50.00	0.90		45.00		

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
									837.00		
	CONSIDERING 70% FOR REMOVING AND RESETTING								585.90		
	Abbigere colony										
	1st A cross road	0.00	28.50	sqm	2	28.50	0.90		51.30		
	3rd A cross road	0.00	40.00	sqm	2	40.00	0.90		72.00		
	4th A cross road	0.00	31.00	sqm	2	31.00	0.90		55.80		
	6th cross road (RHS)	0.00	59.00	sqm	2	59.00	0.90		106.20		
	Total								871.20	49.06	42,739.37
6	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surface on both sides etc, and complete as per the directions of Engineer in charges. (Data Rate)										
	For Drain Cover Slabs										
	Main road	0.00	200.00	Sqm	1	200.00	0.90		180.00		
	1st cross road	0.00	85.00	Sqm	2	85.00	0.90		153.00		
	2nd cross road	0.00	130.00	Sqm	2	130.00	0.90		234.00		
	3rd cross road	0.00	110.00	Sqm	2	110.00	0.90		198.00		
	5th cross road	0.00	30.00	Sqm	1	30.00	0.90		27.00		
	6th cross road	0.00	50.00	Sqm	1	50.00	0.90		45.00		
	Total								837.00		
	considering 30% for new precast slab								251.10		
	Abbigere colony										
	1st A cross road	0.00	28.50	sqm	2	28.50	0.90		51.30		
	3rd A cross road	0.00	40.00	sqm	2	40.00	0.90		72.00		
	4th A cross road	0.00	31.00	sqm	2	31.00	0.90		55.80		
	6th cross road (RHS)	0.00	59.00	sqm	2	59.00	0.90		106.20		
	Total								536.40	1615.00	8,66,286.00
7	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials separately complete as per specifications. MORTH Specification No. 202 (PW,P & ISTD SR 2018-19, Item No. 18.47, Page No.140)										
	Road Formation										
	Main road	0.00	200.00	cum	1	200.00	4.50	0.15	135.00		
	1st cross road	0.00	85.00	cum	1	85.00	3.00	0.15	38.25		
	2nd cross road	0.00	130.00	cum	1	130.00	4.20	0.15	81.90		
	3rd cross road	0.00	110.00	cum	1	110.00	4.20	0.15	69.30		
	5th cross road	0.00	30.00	cum	1	30.00	4.20	0.15	18.90		
	6th cross road	0.00	50.00	cum	1	50.00	4.00	0.15	30.00		
	Total								373.35	952.94	3,55,780.15
8	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by mechanical means attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3 (PW,P & ISTD SR 2018-19, Item No. 19.56, Page No.146)										
	Abbigere colony										
	Road Formation										

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
	1st A cross road	0.00	28.50	sqm	1	28.50	3.50	0.00	99.75		
	3rd A cross road	0.00	40.00	sqm	1	40.00	4.60	0.00	184.00		
	4th A cross road	0.00	31.00	sqm	1	31.00	4.10	0.00	127.10		
	6th cross road (RHS)	0.00	59.00	sqm	1	59.00	4.50	0.00	265.50		
	Total								676.35	41.34	27,960.31
9	KSRRB 300-48. Scarifying kankar / gravel / metal crust by mechanical means upto 150mm thick, disposal of stuff including cost of all labour charges, HOM complete as per specifications. MORTH / Chapter 3 (PW,P & IWTD SR 2018-19, Item No. 19.54, Page No.146)										
	Road Formation										
	Main road	0.00	200.00	Sqm	1	200.00	4.50		900.00		
	1st cross road	0.00	85.00	Sqm	1	85.00	3.00		255.00		
	2nd cross road	0.00	130.00	Sqm	1	130.00	4.20		546.00		
	3rd cross road	0.00	110.00	Sqm	1	110.00	4.20		462.00		
	5th cross road	0.00	30.00	Sqm	1	30.00	4.20		126.00		
	6th cross road	0.00	50.00	Sqm	1	50.00	4.00		200.00		
	Abbigere colony										
	1st A cross road	0.00	28.50	sqm	1	28.50	3.50		99.75		
	3rd A cross road	0.00	40.00	sqm	1	40.00	4.60		184.00		
	4th A cross road	0.00	31.00	sqm	1	31.00	4.10		127.10		
	6th cross road (RHS)	0.00	59.00	sqm	1	59.00	4.50		265.50		
	Total								3165.35	25.44	80,526.50
10	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occurring during rolling including cost of all labour, HOM complete as per specifications. MORTH I Chapter 3 (PW,P& IWTD SR 2018-19, Pg No 147 Item No.19.64)										
	Road Formation										
	Main road	0.00	200.00	Sqm	1	200.00	4.50		900.00		
	1st cross road	0.00	85.00	Sqm	1	85.00	3.00		255.00		
	2nd cross road	0.00	130.00	Sqm	1	130.00	4.20		546.00		
	3rd cross road	0.00	110.00	Sqm	1	110.00	4.20		462.00		
	5th cross road	0.00	30.00	Sqm	1	30.00	4.20		126.00		
	6th cross road	0.00	50.00	Sqm	1	50.00	4.00		200.00		
	Abbigere colony										
	1st A cross road	0.00	28.50	sqm	1	28.50	3.50		99.75		
	3rd A cross road	0.00	40.00	sqm	1	40.00	4.60		184.00		
	4th A cross road	0.00	31.00	sqm	1	31.00	4.10		127.10		
	6th cross road (RHS)	0.00	59.00	sqm	1	59.00	4.50		265.50		
	Total								3165.35	6.36	20,131.63
11	KSRRB M400-17. Providing, laying, spreading and compacting Crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No.406. (PW,P& IWTD SR 2018-19, Pg No 155, Item No. 20.18)										
	Road Formation										
	Main road	0.00	200.00	cum	1	200.00	4.50	0.10	90.00		
	1st cross road	0.00	85.00	cum	1	85.00	3.00	0.10	25.50		
	2nd cross road	0.00	130.00	cum	1	130.00	4.20	0.10	54.60		
	3rd cross road	0.00	110.00	cum	1	110.00	4.20	0.10	46.20		
	5th cross road	0.00	30.00	cum	1	30.00	4.20	0.10	12.60		
	6th cross road	0.00	50.00	cum	1	50.00	4.00	0.10	20.00		

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
	Abbigere colony										
	1st A cross road	0.00	28.50	Cum	1	28.50	3.50	0.100	9.98		
	3rd A cross road	0.00	40.00	Cum	1	40.00	4.60	0.100	18.40		
	4th A cross road	0.00	31.00	cum	1	31.00	4.10	0.100	12.71		
	6th cross road (RHS)	0.00	59.00	cum	1	59.00	4.50	0.100	26.55		
									316.54	2001.28	6,33,475.16
	CONCRETE PAVEMENT										
	KSRRB M600- Cement Concrete Pavements										
12	KSRRB M600-1. Providing and Constructing dry lean cement concrete mix CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016, aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. Clause 601 of MORTH V Revision and IS 456 Table-5 -do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. (PW,P& I WTD SR 2018-19 P-174, I-22.1.2)										
	DLC										
	Main road	0.00	200.00	Cum	1	200.00	4.50	0.10	90.00		
	1st cross road	0.00	85.00	Cum	1	85.00	3.00	0.10	25.50		
	2nd cross road	0.00	130.00	Cum	1	130.00	4.20	0.10	54.60		
	3rd cross road	0.00	110.00	Cum	1	110.00	4.20	0.10	46.20		
	5th cross road	0.00	30.00	Cum	1	30.00	4.20	0.10	12.60		
	6th cross road	0.00	50.00	Cum	1	50.00	4.00	0.10	20.00		
	Abbigere colony										
	1st A cross road	0.00	28.50	cum	1	28.50	3.50	0.10	9.98		
	3rd A cross road	0.00	40.00	cum	1	40.00	4.60	0.10	18.40		
	4th A cross road	0.00	31.00	cum	1	31.00	4.10	0.10	12.71		
	6th cross road (RHS)	0.00	59.00	cum	1	59.00	4.50	0.10	26.55		
									316.54	3944.51	12,48,575.19
13	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum, Coarse and fine aggregate conforming to IS: 383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour, hire charges of machineries, all lead & lift charges etc., complete as per specifications. -do- with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. (PW,P& I WTD SR 2018-19, Pg No 176 Item No. 22.6.1)										
	New CC Road										
	Main road	0.00	200.00	Cum	1	200.00	4.50	0.16	144.00		
	1st cross road	0.00	85.00	Cum	1	85.00	3.00	0.16	40.80		
	2nd cross road	0.00	130.00	Cum	1	130.00	4.20	0.16	87.36		
	3rd cross road	0.00	110.00	Cum	1	110.00	4.20	0.16	73.92		
	5th cross road	0.00	30.00	Cum	1	30.00	4.20	0.16	20.16		
	6th cross road	0.00	50.00	Cum	1	50.00	4.00	0.16	32.00		
	Abbigere colony										
	1st A cross road	0.00	28.50	Cum	1	28.50	3.50	0.16	15.96		

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.	
		from	to									
	3rd A cross road	0.00	40.00	Cum	1	40.00	4.60	0.16	29.44			
	4th A cross road	0.00	31.00	Cum	1	31.00	4.10	0.16	20.34			
	6th cross road (RHS)	0.00	59.00	Cum	1	59.00	4.50	0.16	42.48			
									506.46	5354.02	27,11,576.48	
14	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. (PW,P& IWTDR SR 2018-19, Pg No 27 Item No.5.30)											
	New Kerb											
	Main road	0.00	200.00	Nos	1	200.00			445.00			
	1st cross road	0.00	85.00	Nos	2	85.00			378.00			
	2nd cross road	0.00	130.00	Nos	2	130.00			578.00			
	3rd cross road	0.00	110.00	Nos	2	110.00			490.00			
	5th cross road	0.00	30.00	Nos	1	30.00			67.00			
	6th cross road	0.00	50.00	Nos	1	50.00			112.00			
	Abbigere colony											
	1st A cross road	0.00	28.50	Nos	2	63.33	28.50 / 0.45		127.00			
	3rd A cross road	0.00	40.00	Nos	2	88.89	40.0 / 0.45		178.00			
	4th A cross road	0.00	31.00	Nos	2	68.89	31.0 / 0.45		138.00			
	6th cross road (RHS)	0.00	59.00	Nos	2	131.11	59.0 / 0.45		262.00			
	Total								2775.00	435.84	12,09,446.32	
15	KSRRB M800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications, MORTH Chapter 8 (PW,P& IWTDR SR 2018-19, Pg No 180, Item No. 24.1)											
	Kerb painting											
	Main road	0.00	200.00	Sqm	1	200.00	0.35		70.00			
	1st cross road	0.00	85.00	Sqm	2	85.00	0.35		59.50			
	2nd cross road	0.00	130.00	Sqm	2	130.00	0.35		91.00			
	3rd cross road	0.00	110.00	Sqm	2	110.00	0.35		77.00			
	5th cross road	0.00	30.00	Sqm	1	30.00	0.35		10.50			
	6th cross road	0.00	50.00	Sqm	1	50.00	0.35		17.50			
	Abbigere colony											
	1st A cross road	0.00	28.50	Sqm	2	28.50	0.40		22.80			
	3rd A cross road	0.00	40.00	Sqm	2	40.00	0.40		32.00			
	4th A cross road	0.00	31.00	Sqm	2	31.00	0.40		24.80			
	6th cross road (RHS)	0.00	59.00	Sqm	2	59.00	0.40		47.20			
	Total								452.30	84.80	38,355.04	
16	KSRRB M300-19 Removal of unserviceable soil including excavation, loading and disposal but excluding replacement by suitable soil which shall be paid separately as per clause 300.5 complete as per specifications MORTH Specification No. 301. (PW,P& IWTDR SR 2018-19, Pg No 144, Item No.19.20)											
	Vide Item No 2.			Cum					481.44			
									481.44	34.98	16,840.69	
17	KSRRB M-100-1 Loading and Unloading of Stone Boulder / Stone aggregate / Sand Kanker / Moorum.KSRRB M100-1 : Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.MORTH -100 / Chapter 1, (PW,P& IWTDR SR 2018-19, Pg No 136, Item No.17.1)											
	Vide Item No 1 ,7 & 9.			Cum					725.90			
									725.90	57.00	41,376.44	

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
18	KSRRB M100-4.1. Cost of haulage Excluding Loading and Unloading MORTH-100/Chapter 1 case-I surface road (PW,P& I WTD SR 2018-19, Pg No 136, Item No.17.4)										
	Vide Item No 16 & 17.			Cum					1207.34		
									1207.34	56.32	67,997.40
19	Filling in foundation with granite/trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications.										
	a) 40mm Jelly.			Cum	15	0.31		0.40	1.87	1901.00	3555.99
						(3.142*0.63*0.63)/4					
	b) 20mm Jelly.			Cum	15	0.31		0.40	1.87	1901.00	3555.99
	c) Coarse sand.			Cum	15	0.31		0.30	1.40	2651.00	3719.20
	d) Fine Sand			Cum	15	0.31		0.20	0.94	2651.00	2479.47
	e) 12.5mm chips			Cum	15	0.31		0.30	1.40	1901.00	2666.99
20	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984- 995 with latest amendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe around to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. (Perforated Pipe for Rain Water Harvesting Pit) (BWSSB SR 2017-18, Pg No 121 Item No. 1.17 Code No. K010Q)										
	0.63m dia HDPE Perforated Pipe. For 1.8 Mtr depth,			Rmt	27.00				27.00		
									27.00	10822.32	292202.68

BRUHAT BENGALURU MAHANAGARA PALIKE

ADMINISTRATIVELY SANCTIONED FOR **R. 3000**
(Rupees) **Ninety nine lakh only**
.....
Under the Head of Account **P-3229 SC-SP/TSP**
Nukya mantigela nava Bangalore
Nava Nayroothane Yotane
Registered **16/11/20** Subject to
to conditions **16/11/2019**
No **EE/OP/As** **16/11/20** **16/11/2019**
JE/AE. **(DASARAHALLI) BBVA**